



Hand Control Unit LWL3

Size	115 x 65x 26 mm (LxWxH)
Housing Material	ABS, inside copper coated
Connection to Controller	by fibre optic line POF or GOF
Operating voltage	3V by 3x1,5V AAA
Operating time by Battery	approx. 30h (while continues usage)
Charger for HCU Unit	available on request
Auto-off	after 20sec.
Keypad	Foil keypad
Temperature range	5°C...+40°C

The Hand Control Unit is designed for usage either inside chamber or even control room. For inside chamber usage, the copper coating and Auto-off function of the electronic guarantee no EMC interference during measurement. The fibre optic connection by POF or optionally GOF single phase cable, reduce the setup time.

The ergonomic designed Foil-Keypad guarantees a comfortable handling during operation. Three illuminated Unit buttons show the actual device in remote operation.

The three status LED's of the Unit Buttons are for indication of low battery voltage, if illuminated at the same time. In standard configuration are 3 AAA Batteries used. An optimal charger and Accumulators available on request.